457.

TUMKUR DIVISION.

The 6th February 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 1st March 1904, for restoring Bugadanhalli tank, Registered No. 304, Tumkur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1904.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Bugadanhalli tank, Registered No. 304, Tumkur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Restoring Bugadanhalli tank, Registered No. 304, Tumkur Taluk.

Items of work.	*Per*	*Quantity.*
Bund—		
Earthwork	C. yd.	12,097
New stone work	„	318
Old stone work with new jelly	„	2,271
Turfing	S. yd.	14,348
Grade stones, new	Each.	42
Index stones	do	42
Register No. stone	do	1
B. M. stones	do	2
No. I Left waste weir 33 ft. long—		
Dismantling the present body wall, etc.	L. S. Rs.	
Burnt brick in chunam	C. ft.	349
Plastering with chunam	Sqr.	2·86
Burnt stone in chunam	C. ft.	776
Burnt stone slabs	S. ft.	760
Concrete	C. f t.	96
Earthwork and turfing to wing bunds	L. S. Rs.	
Re-setting apron	Do	
No. II Left waste weir 215 ft. long—		
Dismantling the present body wall, etc.	L. S. Rs.	
Burnt brick in chunam	C. ft.	999
Chunam plastering	Sqr.	7·19
Burnt stone in chunam	C. ft.	1,276
Burnt stone slabs	S. ft.	2,756
Concrete	C. ft.	326
Earthwork and turfing to wing bunds	L. S. Rs.	
Re-setting apron	Dc	
No. III Right waste weir 166 ft. long—		
Excavating foundation and forming wing bund including turfing	L. S. Rs.	
Burnt brick in chunam	C. ft.	1,080
Burnt stone slabs	S. ft.	270
Plastering	Sqr.	3·03
Rough stone apron	C. yd.	74

C. MADHAVA ROW, *Offg. Executive Engineer.*